

Melissia Cardona
ECD:7/10/17

320 W 36st


DID#1482042
CJ#815319

Ver. 2/8/2017

CHARTER COMMUNICATIONS SCOPE OF WORK

Project Information (Will populate into Contact Cost tab)			
NAME:	Six Continents Hotel - Crowne Plaza		
ADDRESS:	320 W 36 Th St NEW YORK MS 10018		
LOB:	COAX COMMERCIAL NEW BUILD	TYPE:	COAX
DOCKID:	1482042	CONSTR#:	815319
POC:	:Darren Milline (212) 912-2125 dmline@flintlockdcl.com		
INODE/HUB:	MANHATTAN SOUTH A/AG06	MAP:	NA
OU:	C133		
REC'D DATE:	Jun 12, 2017 (CST)	WALKED BY:	hylan
Serviceability Code			
MTU, STU or NEX	MTU		
BUILD TYPE			
TENANT COUNT			
LENGTH OF BLDG			
WIDTH OF BLDG			
NUMBER OF STORIES	26		
BUILDING EXTERIOR FINISH			
COMMON MPOE AVAILABLE			
COMMON MPOE LOCATION			
COMMON MPOE ROOM ACCESS SPECIFICS			
PRIVATE NON-MPOE EQUIPMENT LOCATION			
POWER IS IT AVAILABLE & WHERE			
RACK or WALL MOUNT			
SPACE AVAILABILITY FOR RACK/WALL MOUNT			
CORES REQUIRED TO ENTER BLDG			
PREBURY DROP			
FIBER VERIFICATION COMPLETED BY			
FIBER VERIFICATION COMPLETE DATE			
Project Description: Detail from Right Of Way to Interior D-Marc in or at the Venue.			
IF MTU, detailed description MUST contain Entire Building Layout, Rack, and Power Locations			
Lateral To Plant Access Point To Basement To Riser Entry:			
Identified existing coax equipments within target building. Node AT66 and power supply are located in basement MDF closet with fiber coming from rear yard through 3" conduit. As per POC Lawrence Smith, tap is needed in MDF closet in basement. New coax from amp 3A at 329 W 35th St rear yard, to run approximately 110' to target, and enter basement along existing fiber through 3" conduit then run open ceiling pathway to MDF closet. Target building is a hotel. Rooms are wired to 9th floor and 19th floor IDF closets. See drawing for footage from MDF in basement to riser location.			
Riser Within Building:			
9th floor IDF closet from 2-1 5th floor			
19th floor IDF closet from 16-26th Building is under construction there is only 1 tenant at the time for basement MDF room			

Alex- 500 Cable Pull	328-2191	PO#808258
----------------------	----------	-----------



BUILDING ACCESS	NAME	PHONE #
NORMAL BUSINESS HOURS	Lawrence Smith	914-450-0461
AFTER HOURS		
EMERGENCY		



328-2141

Coax Activation Documentation WorksheetDate: 9/1/17 CJ #: 815319 DID #: 1482042Town: Southern Manhattan Address: 320 W 36th StContractor Company: Hylan Data Technician Name: _____

Node Location: _____ Node Number: _____ Node Port: _____

Coax

- 1, Complete coax work order build prior to following the steps below.
- 2, Verify all required reporting parties are notified of potential interruption, for known customer disruption-initiate a NODE SUSPENSION before active plant work is initiated.
- 3, Verify Tie-Point is active with both RF & AC on seizure assembly.
- Volts #: _____ Low Channel #: _____ High Channel #: _____
- 4, Verify no-short on work order extension feed cable.
- 5, Connect the completed coax extension job with Tie-Point.
- 6, Verify for both RF & AC on Tie-Point seizure assembly-if no RF and AC present, disconnect extension and trouble shoot extension.
- 7, If Tie-Point verifies as good, then setup remainder of extension.
- 8, Take and record Amp & Termination RF readings, clear plant from reporting parties and NODE SUSPENSION

Amp #: SA Volts #: 60 Low Channel: 21 / 37.1 High Channel: 24 / 47.1

Amp #: _____ Volts #: _____ Low Channel: _____ / _____ High Channel: _____ / _____

Amp #: _____ Volts #: _____ Low Channel: _____ / _____ High Channel: _____ / _____

Termination tap value: 23-8 Low Channel: 12.6 High Channel: 21.7

Termination tap value: _____ Low Channel: _____ High Channel: _____

Termination tap value: _____ Low Channel: _____ High Channel: _____

Comments: _____

SIX CONTINENTS HOTEL - CROWNE PLAZA
 320 W 36 TH ST NEW YORK MS NY 10018
 LOB COAX COMMERCIAL NEW BUILD
 DOCKID 1482042 CONST# 815319/NA SITE SURVEY# 815319A
 POC: DARREN MILINE 212-912-2125
 NODE/HUB AG06 MANHATTAN SOUTH A MAP 113-103
 DESIGN 6-28-2017
 OU C133

AFTER RISER

- = Splices
 - = 500 cable
 - = Building Rear.
 o = Fire stop

STEP #4
 RISER UP 90' OF NEW 500 CABLE TO
 THE 9TH FLOOR AND INSERT/SPLICE IN
 NEW 20/8 TAP
 PLACE TERM

Tie in point Rear
 at 329 W 35th St.

STEP #5
 PLACE NEW LE AND
 INSERT/SPLICE NEW 23/8
 FEEDING BSMT OF TARGET

